



SPECIFICATION

1. PROVIDING & LAYING IN CEMENT CONCRETE 1:4:8 SHANKER GARH BALLAST 40MM APPROVED FINE SAND & CEMENT IN FOUNDATIONS.
2. PROVIDING & INJECTING CHEMICAL EMULSION FOR PRE CONSTRUCTION ANT TERMITE TREATMENT
3. R.C.C. WORK 1:1.5:3 WITH CEMENT APPROVED COARSE SAND 2 CM GAUGE APPROVED BALLAST IN R.C.C. COLUMNS & FOOTING
4. R.C.C. PLINTH BEAM 0.45M THICK IN 1:1.5:3.
5. FIRST CLASS B/W IN FOUNDATION & SUPER STRUCTURE 1:6 CEMENT & COARSE SAND.
6. R.C.C. LINTEL & SUNSHADE IN 1:2:4 CEMENT COARSE SAND & 2 CM GAUGE STONE BALLAST.
7. 0.15 M THICK R.C.C. SLAB WITH 1:1.5:3 CEMENT COARSE SAND & 2 CM GAUGE STONE BALLAST.
8. 12 MM THICK PLASTER ON PLASTER ON WALL 1:6 CEMENT SAND & PLASTER ON CEILING IN 1:4 CEMENT SAND.
9. 100 MM DIA. RAIN WATER PIPES.

SCHDULE FOR OPENING

1. DOORS - 1.21 M X 2.13 M
2. WINDOWS - 2.44 M X 1.52 M

AREA DETAILS

1. TOTAL LAND AREA -	2,530.00 SQUIRE METRE
2. TOTAL LAND AREA -	27,222.00 SQUIRE FEET
3. TOTAL BUILT UP AREA GROUND FLOOR -	878.00 SQUIRE METRE
4. TOTAL BUILT UP AREA GROUND FLOOR -	9,451.00 SQUIRE FEET
5. TOTAL BUILT UP AREA FIRST FLOOR -	878.00 SQUIRE METRE
6. TOTAL BUILT UP AREA FIRST FLOOR -	9,451.00 SQUIRE FEET
7. TOTAL BUILT UP AREA BOTH FLOOR -	1,756.00 SQUIRE METRE
8. TOTAL BUILT UP AREA BOTH FLOOR -	18,902.00 SQUIRE FEET
9. PLAY GROUND AREA (APPROX.) -	1,000.00 SQUIRE METRE
10. PARKING AREA (APPROX.) -	150.00 SQUIRE METRE

NOTE:-

1. THERE IS NO ANY GOVT. PROPERTY IN 30 METRE RADIUS.
2. ALL DETAILS OF THE SITE IS GIVEN BY THE PARTY.
3. ALL DIMENTION IN FEET.

PROPOSED B.Ed. BUILDING PLAN OF DAYA RAM VERMA MAHAVIDYALAYA AT GATA NO. 353 (TOTAL AREA OF ABOVE GATA No. 0.2530 HECTARE) AT PITHAPUR, KATEHRI, PARGANA & TEHSIL- AKBARPUR, DISTT. AMBEDKAR NAGAR (U.P.)

SIGNATURE OF OWNER:-

SIGNATURE OF DESIGNER:-

अमित प्रकाश
L.No. D-31A.F.D.A
[Signature]